

City of Cleveland Justin M. Bibb, Mayor

Department of Finance Division of Purchases & Supplies 601 Lakeside Avenue, Room 128 Cleveland, Ohio 44114-1080 216/664-2620 • Fax: 216/664-2177 www.cleveland-oh.gov

June 14, 2024

ADDENDUM 5

BID TITLE: File No. 55-24 Green Road Pump Station

BID DUE: Thursday, July 18, 2024 at 12 o'clock noon (Eastern Time)

Attention Bidders:

We have been requested to issue the addendum for the following:

Please ensure that a copy of this addendum is included and returned with the bid specifications furnished to you by this office, as it will have the same force and effect as if it were part of the specifications originally issued.

- 1. Extend the bid opening date.
- 2. Extend the last day for questions.
- 3. Remind potential bidders of the OEO participation goals.
- 4. Make changes to the specifications.
- 5. Make changes to the contract drawings.
- 6. Answer questions received.

If you have any questions regarding the attached, please contact Jules Gilliam at 216-664-2621. Thank you for your prompt attention and assistance in this matter.

Signature of Potential Bidder & Name of Company

Today's Date

Thank you, ONIO

Donia Patterson, Assistant Administrator Purchases & Supplies CC: Attachments

ADDENDUM NO. 5

The bid due date is extended to July 18, 2024 and bids must be date stamped no later than 11:59 a.m. that day.

The last day for questions is extended to July 8, 2024 by 12:00 p.m.

OEO Participation Goals

• Reminder that the OEO participation goals are 15%/MBE, 7%/FBE, and 8%/CSB. Please make a good faith effort to meet the goals.

Changes to the Specifications:

1. Section 32 31 13 – Chain Link Fence and Gates is deleted. Refer to the detail on sheet C-03 for ornamental security gate requirements.

Changes to the Contract Drawings:

- 1. C-01 Showing approximate routing of gas service.
- 2. C-03 The gate detail was revised to reflect an ornamental security gate instead of a chain link gate, to match the rest of the existing gate.
- 3. I-05 thru I-10 and I-20 Revised to include an intermediate position limit switch on the discharge check valves, and to include check valve closed as a start permissive for the pumps.
- 4. E-12 Revised to add a CAT6 cable from each pump local control panel to the master control panel.

Answers to questions received:

1. There is a discrepancy in the duration of the guarantee period on the project. General Conditions B-38 states the guarantee period is 12 months. Supplemental General Conditions C-12 for insurance says there is a 24 month period. Please clarify.

Answer: C-12 supplements B-38, so 24 months is the guarantee period.

2. The ball check valves with hydraulic actuators are specified to operate with slow and fast speeds. At other CWD pump stations this is done with open, intermediate (20% open) and closed limit switches mounted on the valve that communicate with the associated pump LCP. The pump LCP then commands solenoid valves on the hydraulic actuator control panel for slow/fast open and closed. These switches and positions are not indicated in the valve specifications or on the ladder diagrams for the pump LCPs. This would provide local control of pumps if the RTU is out of service. Please provide additional information on the logic for opening and closing the ball check valves in coordination with pump start/stop.

ADDENDUM NO. 5

Answer: The ball check valves shall include an intermediate limit switch in addition to the open and closed limit switches. Ladder diagrams have been modified to incorporate the intermediate limit switches and slow and open commands.

3. The pump LCP sequence of control does not indicate that the ball check valves being closed is a permissive for pump start. This permissive is common at other locations.

Answer: Ladder diagrams have been modified to add a relay indicating ball check valve closed position, and adding that relay as a start permissive for pump start.

4. The ladder diagrams for the pump LCPs show two solenoids for operation of the hydraulic cylinders. Please provide additional detail on the purpose of each solenoid valve and their sequencing with ball check valve position and pump start/stop.

Answer: Please see line 1044 of the schematic on sheet I-10. This shows the startup sequence for the pumps. After pump start, and following a 5-second timer, switch TD1 closes, powering both solenoids. The normally open solenoid closes and the normally closed solenoid opens, opening the discharge control valve (ball check valve).

5. Please confirm the existing first floor slab can support loading imposed by construction loading. For example a 36" gate valve can weigh between 4-5 tons.

Answer: EL 1131.50 slab has a design load rating of 200 psf. It is the Contractor's responsibility to determine the means and methods to ensure the safety of the structure during construction.

6. The existing louvers have operable/lockable security bars on the exterior of the building. Are the new louvers to have new lockable/operable security bars?

Answer: Security bars to be removed, but not replaced.

7. Please confirm that the existing overhead door is to remain. Only the operator and weather stripping is to be replaced.

Answer: Existing overhead door not to be replaced.

8. Drawing I-04 currently only shows chlorine from the water quality panel. There are a number of other instruments on the water quality panel that are not shown on the drawings. Do those need to be added to the loop drawings?

Answer: The chlorine analyzer is separate from the water quality panel. Currently the RTU only receives a signal from the chlorine analyzer and does not receive any signals from the water quality panel. The new PLC matches this, therefore, no instruments from the water quality panel need to be added.

9. Where is the existing water quality panel to remain to sample water from?

ADDENDUM NO. 5

Answer: No modifications are being made to the existing water quality panel under this project.

10. The mechanical drawings state to refer to the structural drawings for pipe support details. However, the only detail supplied is for pipe straps connected to concrete thrust blocks. Will a detail be provided for the pipe stand and various valve supports?

Answer: Pipe support detail is found on lower left corner of sheet S-03.

11. Per plan, portions of the existing concrete driveway are removed and replaced. However, there are no details for said repairs within the plans for concrete drives. Can a detail be provided for these replacements/repairs?

Answer: See sheet S-03.

12. I am looking at the Green Rd Pump Station project. Concerning the gates. Drawing C-01 shows a single leaf 18' wide gate. The chain link detail on C-03 shows a double gate.

Answer: Both C-01 and C-03 show a vehicle access gate and pedestrian gate.

13. The specification 32-31-13 page 3 Part 2 - Products calls for Sch 80 pipe. This is not readily available and would be cost prohibitive for such a small quantity. SS-40 pipe is the most common used today and is a stock material.

Answer: SS-40 pipe is acceptable.

14. Is there an electric gate operator for the 18' gate, if so what is the voltage and how is it going to operate. A slide gate with an operator would be much better. Call with any questions.

Answer: No electric operator, manual swing gate only.

15. See question below from the RTU supplier. We are working on the bid for this project and have discovered that the existing RTU cannot support the additional I/O required for the project. The only solution would be to add an additional Remote I/O cabinet next to the relocated RTU panel. Can you send in a question to see if there will be room to add another cabinet because existing RTU panel cannot support or be modified to add additional I/O. We need to add a Remote I/O panel that will house all new I/O and new HMI. In addition we will need to upgrade the exiting HSQ RTU processor to support the Remote I/O software. Existing RTU is running DOS. We would need to add

3- DI Boards 1-DO Board 1-AI Board 1_AO board

ADDENDUM NO. 5

6 additional I/o boards, plus upgrade Processor, replace power supply to 10 amp, replace power control Board and add an ethernet switch for connection the new HMI display on for of existing RTU panel.

One option is to add the additional RIO panel for the added I/O in separate enclosure and include the HMI in that panel.

Second Option is to convert the new Marshalling panel (Terminal Block panel) to the RIO panel as one. This way you can keep the existing RTU panel (Relocated with above mentioned modifications) and terminate all new I/O direct to the RIO PLC and have one less point of connection failure.

I believe the second option would be the most cost effective. (Sketch included)

Answer: See drawing changes related to RTU and PLC panels in Addendum No. 3.

16. Vibration testing is discussed in general specs as well as pump spec. In pump spec it is listed in the field test section only -- 3rd party vibration. Please advise if FEA analysis is to be conducted by Xylem or 3rd party prior to manufacturing as well. One part of the spec states flow conditioning basket and that the pumps have 18" submergence.

Answer: Third party vibration analysis is required. FEA is not required per the specifications, but the supplier's vibration analyst's Professional Engineer must be experienced in preparing FEA, per 01 61 00 1.02.B.4.a. Please clarify question regarding flow conditioning basket and submergence.

Section 400500 – Pipe Schedule for PW (System 10): Exposed ductile iron service notes cement lining for pipe and fusion bonded epoxy coated. However, section 099100 2.02.D (interior non-submerged ferrous metals) notes a shop primer such as Tnemec N69. Is the interior process ductile iron pipe to be provided as cement lined with a shop applied epoxy primer or to be fusion bonded epoxy lined and coated? Please clarify.

Answer: 09 91 00 2.02D is not intended to apply to process piping. The requirements of 40 05 00 System 10 govern coatings for potable water pipe.

18. We are interested in having Integrity Pump & Motor named as an acceptable manufacturer for Section 43 24 05 (Vertical Suspended Centrifugal Pumps) via addendum. Integrity has confirmed they can meet the specifications and I have attached a curve for your consideration.

Answer: We do not add vendors to approved lists during the bid process. When it says, "or Engineer approved equal", that means at the pre-construction meeting, the winning Contractor using Section 01 25 00 can request substitutions.

19. Please confirm that the owner can isolate the pipe in the basement of the pump station of the building by utilizing existing buried valves outside of the pump station.

Answer: Yes.

20. Will the overhead crane be permitted for use by the contractor for the duration of the contract?

ADDENDUM NO. 5

Answer: Yes.

21. On Drawing E-04 it shows a welding outlet & a 480 outlet on the one-line. I could not find them on the electrical drawings for their actual location. Please confirm the welding/480v outlet location.

Answer: Receptacles shown on E-09, Basement Lighting Plan, on the East wall.

22. Are there any pipe spools, fittings, valves, couplings, etc. on the interior PW lines that are to have Class 250 drilled flanges? The specs contain some conflicting information regarding flanges and the Ball Valve spec for 6" to 24" ball valves references Class 250 flanges. However, the plans and specs do not specifically note where or if any flanges should be drilled to class 125 or 250. Please clarify.

Answer: The design working pressure for the suction pipe, flanges, and valves is 150 PSI, and suction pipe and flanges shall be Pressure Class 150. The design working pressure for the discharge pipe, flanges, and valves is 250 PSI, and discharge pipe and flanges shall be Pressure Class 250. Pump suction and discharge flanges shall be provided to match pressure rating and flanges of supplied ductile iron pipe. Ball valves are Pressure Class 250 as stated in the Contract Documents.

23. There may still be some confusion on the working pressure ratings versus flange class drilling for the ductile iron pipe, fittings, valves, couplings etc. I am writing to try to confirm what the intent is for the discharge piping, fittings, valves, etc. - ANSI/ASME 125/250 standards refer to grey iron while 150/300 refer to ductile iron The flange O.D. and drilling pattern is the same for Class 125 and Class 150 flanges. The flange O.D. and drilling pattern is the same for Class 250 and Class 300 flanges. - Class 125/150 flanges do not mate up with class 250/300 flanges (drilling patterns and class 250/300 will achieve higher pressure ratings than 125/150. bolt sizing differ) Clarification: When you refer to 250 psi, are you referring to the class of flange and its drilling pattern or are you referring to the minimum working pressure of 250psi that the flanges must meet? I ask because 250 flange class and 250 PSI have been used at the same time in the plans, specs and Addendum 3 and can be contradicting at times. If Class 250/300 flanges are required, all pipe, fittings, couplings, pumps, valves etc on the discharge side must be drilled to that pattern in order to mate up. The pump spec makes a reference to ASME B16.1 125/150 lb discharge head flange. The ball valve spec references Class 250 flanges.

Answer: See answer to No. 22 above.

24. On the North side of the pump station the contractor is to replace 2 sections of piping on the 36" and 24" intake/discharge lines to a point 2.5' outside of the building. When excavating for the 36" stub there is an existing electrical feed designated to be protected, however, the plans do not show where this feed runs to and what it is feeding. Please indicate the feeder location and connection voltage as this connection will need to be temporarily removed and reworked.

ADDENDUM NO. 5

Answer: Generator power conduits that run East of the 36" line shall be protected during excavation. The voltage of the generator feed is 480V, 3PH. See sheet E07. An existing 16" valve vault and chlorine vault are also routed through this area and shall be protected. Contractor to verify any other existing duct banks that leave the North wall and are impacted by the excavation.

25. On the North side of the pump station the contractor is to replace 2 sections of piping on the 36" and 24" intake/discharge lines to a point 2.5' outside of the building. When excavating for the 36" stub there is an existing gas meter/feed shown on the plans, however, the gas line service from the main is not shown in the plans. Please indicate approximate routing of gas line from the main to the meter and the specific size/material of the existing service.

Answer: See revised C-01 in this addendum showing approximate routing of gas service. Based on Dominion East Ohio provided information, gas service is assumed to be 1" steel.

26. On the bid drawings, the one line of the MCC differs with the elevation, we need confirmation which is correct. If it is the elevation, the one line needs to be adjusted to give the appropriate sizes/ratings needed.

Answer: It is unclear where the discrepancy between the MCC one-line diagram and elevation exists. Contractor to clarify the exact discrepancy in question. See response to No. 27 for clarification on one-line diagram and the elevation.

27. There is an MLO section in the MCC elevation graphic, which is not shown on the one line. Is it to be included in the MCC?

Answer: The MLO section is for the existing standby generator connection as shown on the one-line diagram. The MLO section shown on elevation on E05 is not explicitly labeled MLO on the one-line diagram on E04.

28. On sheet, E-12, Note #4 states the contractor is responsible for field verifying quantities of fire alarm devices and reworking all existing fire alarm conduit and cable. Since there are no more site visits, can the locations and quantities of these devices be located on the drawings to allow for an accurate and competitive bid?

Answer: Contractor scope of Work is as stated in the Contract Documents; to field verify the existing FACP devices. Existing fire alarm control system generally includes 3-4 smoke detectors in the main pump room, 2-3 audio/visual notification devices on the building exterior at the mandoors. Final quantity and location to be verified by Contractor.

29. On sheet, E-12, Note #2 states that from the junction box to the Gate house is all existing cable & conduit. Can you please provide a location of this existing junction box that leads to the gate house?

Answer: Junction boxes proposed for the Gate House are proposed new. Provide new junction boxes on the exterior wall to allow for splice connections to the existing conductors.

ADDENDUM NO. 5

30. On sheet, E-12, Note #3 states that from the junction box to the 36" Valve Vault is all existing cable & conduit. Can you please provide a location of this existing junction box that leads to the 36" Valve Vault?

Answer: Junction boxes proposed for the 36" Valve Vault are proposed new. Provide new junction boxes on the exterior wall to allow for splice connections to the existing conductors.

31. Can the location of all existing circuits/devices that will be modified into the new LP-2 & LP-3 panelboards be shown on the site drawings?

Answer: For panelboard circuits located on the interior of the building see Electrical plan views for equipment locations. See Civil site plans for location of exterior circuits (16" and 30" valve vaults, etc.).





2 WORKING DAYS BEFORE YOU DIG CALL TOLL FREE 800-362-2764 NON-MEMBERS MUST BE CALLED DIRECT UNDERGROUND UTILITIES 2 WORKING DAYS BEFORE YOU DIG



GENERAL SHEET NOTES

- FIELD VERIFY ALL SURFACE FEATURES AND UTILITIES PRIOR TO INITIATING SITE WORK.
- COORDINATE WITH UTILITY OWNERS FOR PROTECTION AND/OR RELOCATION OF EXISTING OVERHEAD UTILITIES.
- SECURE THE SITE AT THE END OF EACH WORK DAY. COORDINATE WITH THE VILLAGE OF HIGHLAND HILLS FOR MAINTENANCE OF TRAFFIC AS REQUIRED TO COMPLETE PROPOSED WORK.
- RESTORE AREAS DISTURBED BY CONSTRUCTION ACTIVITIES IN KIND AND AS SHOWN ON C-02.
- ADDITIONAL STAGING AREAS REQUIRED FOR CONSTRUCTION ARE THE RESPONSIBILITY OF THE CONTRACTOR.
- INSTALL AN 8-INCH DUCTILE IRON CASING PIPE TO CARRY THE TWO (2) 1-INCH SCHEDULE 40 PVC PIPES LOCATED DOWNSTREAM AND UPSTREAM THE EXISTING VENTURI METER AS SHOWN WITH FOUR (4) FEET MINIMUM COVER. CONTRACTOR SHALL ALSO INSTALL TWO SPARE 1-INCH SCHEDULE 40 PVC PIPE WITHIN EACH CASING PIPE AND CAP AT EACH END. ALL PIPING SHALL BE INSTALLED TO REDUCE THE NUMBER OF BENDS AND SLOPED TO AVOID HIGH POINTS.
- CORE THROUGH EXISTING STRUCTURE WITH A 2-INCH MINIMUM ANNULUS AND BACKFILL WITH NONSHRINK GROUT AND HYDROPHILIC WATERSTOP.
- INSTALL 6-INCH DUCTILE IRON STORM PIPE THAT CONNECTS TO ROOF DOWNSPOUTS AND DAYLIGHTS UPSTREAM THE EXISTING 18" CMP CULVERTED PIPE AS SHOWN. PIPE SLOPE AND COVER SHALL BE MAXIMIZED BASED ON EXISTING ELEVATIONS. CONCRETE DRIVEWAY SHALL BE SAWCUT AND REPLACED IN KIND TO INSTALL PIPE.
- 10. INSTALL DIFFERENTIAL PRESSURE SENSOR INSIDE PUMP BUILDING.
- 1. REPLACE 2.5FT OF PIPE OUTSIDE OF WALL. SEE SHEET M-07 FOR DETAIL. REFER TO SPECIFICATIONS FOR EXCAVATION AND TEMPORARY EXCAVATION SUPPORT REQUIREMENTS.
- 12. EXISTING SERVICE ENTRANCE RATED CIRCUIT BREAKERS TO BE REMOVED AND TEMPORARILY STORED FOR CONCRETE PAD AND ASSOCIATED CONDUIT REPLACEMENT. CIRCUIT BREAKER SHALL BE REINSTALLED AFTER CONCRETE PAD AND CONDUIT INSTALLATION. SEE ELECTRICAL DRAWINGS FOR MORE INFORMATION.
- 13. EXISTING PAD-MOUNTED TRANSFORMER TO BE REMOVED AND TEMPORARILY STORED BY FIRST ENERGY AND CONCRETE PAD REPLACEMENT. FIRST ENERGY SHALL REINSTALL AFTER CONCRETE PAD AND CONDUIT INSTALLATION. SEE ELECTRICAL DRAWINGS FOR MORE INFORMATION.
- 14. IF TREE CANNOT BE PROTECTED DURING CONSTRUCTION, CONTRACTOR TO REPLACE IN KIND DURING RESTORATION OF SITE.

HORIZONTAL SCALE : 1" = 20'

F	REVISIONS			CITY OF CLEVELAN	D
NO	DATE	BY]		
				CLEVELAND DIVISION OF WA DEPARTMENT OF PUBLIC UTILITI CLEVELAND, OHIO	ATER es
			SUBJECT	CYCLE H - GREEN PUMP STAT	ΓΙΟΝ
			-	SITE PLAN	
DRAW	N BY:	VKN	SCALE	CWD NO:	SHEET NO:
DESIG	NED BY:	AD	1"=20'	-	C-01
CHECH	KED BY:	AJA	DATE: 12/2021		001



		M NO. 3 - FILE NO. 55-24
ADERGROUND UTILITIES 2 WORKING DAYS BEFORE YOU DIG L TOLL FREE 800-362-2764 <u>OHD UTILITES PROTECTION SERVICE</u> MEMBERS MUST BE CALLED DIRECT IDERGROUND UTILITIES 2 WORKING DAYS	HDDENDO	Under the the tot of the
BEFORE YOU DIG CONTRACTOR L TOLL FREE 800-925-0988 OL & GAS PRODUCERS UNDERGROUND PROTECTION SERVICE (OGPUPS)		P. YOUR SERVICE

TE· 12/2021

HECKED BY: AJA





OHIO UTILITIES PROTECTION SERVICE NON-MEMBERS MUST BE CALLED DIRECT UNDERGROUND UTILITIES 2 WORKING DAYS BEFORE YOU DIG CALL TOLL FREE 800-925-0988 OIL + GAS PRODUCERS UNDERGROUND PROTECTION SERVICE {OGPUPS}

	NO	DATE	BY			-
4					CIEVELAND DIVISION OF W	ATED
4						AIEN Es
					CLEVELAND, OHIO	Eð
				SUBJECT	CYCLE H - GREEN PUMP STAT	ION
					PUMP NO. 1 P&ID	
	DRAWI	N BY:	SJT	SCALE	CWD NO:	SHEET NO:
	DESIG	NED BY:	SJT	NTS	_	1-05
	CHECK	ED BY:	VM	DATE: 12/2021		1.00

	A. INSTALL A NEW PLC IN THE NEW MAIN CONTROL PANEL.	
C HMI	B. EXISTING RTU PANEL TO BE RELOCATED. ALL I/O TO BE HARDWIRED TO THE NEW MAIN CONTROL PANEL AND PUMP LOCAL CONTROL PANELS AS SHOWN ON THE DRAWINGS. THE RELOCATED RTU WILL COMMUNICATE WITH THE MAIN CONTROL PANEL VIA AN ETHERNET CONNECTION.	FOR
B RTU	C. UPDATE EXISTING HMI AT THE PARMA CONTROL CENTER TO INCLUDE THE NEW I/O AND CONTROL SHOWN ON THE DESIGN DRAWINGS.	
	D. INTERLOCK REPRESENTS A SINGLE ETHERNET CONNECTION BETWEEN THE MCP AND THE RTU. SHOWN ON MULTIPLE DRAWINGS FOR CLARITY.	INS
<pre></pre>	E. 01-RIO-02 IS LOCATED IN THE PUMP NO. 2 LOCAL CONTROL PANEL 01-LCP-02.	
───────────────────────────── FIELD	F. INTERLOCK REPRESENTS AN ETHERNET CONNECTION BETWEEN 01-RIO-02 AND 01-MCP-01.	
		-

F	REVISIO	ONS		ΓΙΤΥ ΟΕ ΓΙ ΕΛΕΙ ΑΝ	
NO	DATE	BY			
			-	CLEVELAND DIVISION OF WA DEPARTMENT OF PUBLIC UTILITIE CLEVELAND, OHIO	A TER es
			SUBJECT	CYCLE H - GREEN PUMP STAT	ION
				PUMP NO. 2 P&ID	
DRAW	'N BY:	SJT	SCALE	CWD NO:	SHEET NO:
DESIG	NED BY:	SJT	NTS	-	I-06
CHEC	KED BY:	VM	DATE: 12/2021		

TO DISCHARGE MANIFOLD

I-04A

	○ CODED NOTES	
	A. INSTALL A NEW PLC IN THE NEW MAIN CONTROL PANEL.	
C HMI	B. EXISTING RTU PANEL TO BE RELOCATED. ALL I/O TO BE HARDWIRED TO THE NEW MAIN CONTROL PANEL AND PUMP LOCAL CONTROL PANELS AS SHOWN ON THE DRAWINGS. THE RELOCATED RTU WILL COMMUNICATE WITH THE MAIN CONTROL PANEL VIA AN ETHERNET CONNECTION.	
B RTU	C. UPDATE EXISTING HMI AT THE PARMA CONTROL CENTER TO INCLUDE THE NEW I/O AND CONTROL SHOWN ON THE DESIGN DRAWINGS.	
	D. INTERLOCK REPRESENTS A SINGLE ETHERNET CONNECTION BETWEEN THE MCP AND THE RTU. SHOWN ON MULTIPLE DRAWINGS FOR CLARITY.	S
E	E. 01-RIO-03 IS LOCATED IN THE PUMP NO. 3 LOCAL CONTROL PANEL 01-LCP-03.	5
└─╯ 01-RIO-03 FIELD	F. INTERLOCK REPRESENTS AN ETHERNET CONNECTION BETWEEN 01-RIO-03 AND 01-MCP-01.	

TO DISCHARC	ΞE
MANIFOLD	
1.044	
1-04A	

	F	REVISIO	DNS		CITY OF CLEVELAN	D
A	NO	DATE	BY			
4 4					CLEVELAND DIVISION OF WA DEPARTMENT OF PUBLIC UTILITIE CLEVELAND, OHIO	ATER ES
				SUBJECT	CYCLE H - GREEN PUMP STAT	ION
					PUMP NO. 3 P&ID	
	DRAW	'N BY:	SJT	SCALE	CWD NO:	SHEET NO:
	DESIG	NED BY:	SJT	NTS	-	I-07
	CHEC	KED BY:	VM	DATE: 12/2021		

	CODED NOTES	
	A. INSTALL A NEW PLC IN THE NEW MAIN CONTROL PANEL.	
C HMI	B. EXISTING RTU PANEL TO BE RELOCATED. ALL I/O TO BE HARDWIRED TO THE NEW MAIN CONTROL PANEL AND PUMP LOCAL CONTROL PANELS AS SHOWN ON THE DRAWINGS. THE RELOCATED RTU WILL COMMUNICATE WITH THE MAIN CONTROL PANEL VIA AN ETHERNET CONNECTION.	FOR
B RTU	C. UPDATE EXISTING HMI AT THE PARMA CONTROL CENTER TO INCLUDE THE NEW I/O AND CONTROL SHOWN ON THE DESIGN DRAWINGS.	
	D. INTERLOCK REPRESENTS A SINGLE ETHERNET CONNECTION BETWEEN THE MCP AND THE RTU. SHOWN ON MULTIPLE DRAWINGS FOR CLARITY.	SU
\[E]	E. 01-RIO-04 IS LOCATED IN THE PUMP NO. 4 LOCAL CONTROL PANEL 01-LCP-04.	5
└── 01-RIO-04 FIELD	F. INTERLOCK REPRESENTS AN ETHERNET CONNECTION BETWEEN 01-RIO-04 AND 01-MCP-01.A	

F	EVISIO	ONS			
NO	DATE	BY	-	CITY OF CLEVELAN	D
			-	CLEVELAND DIVISION OF WARD DEPARTMENT OF PUBLIC UTILITI CLEVELAND, OHIO	ATER ES
			SUBJECT	CYCLE H - GREEN PUMP STAT	ΓΙΟΝ
				PUMP NO. 4 P&ID	
			1		
DRAW	N BY:	SJT	SCALE	CWD NO:	SHEET NO:
					-

TO DISCHARGE MANIFOLD

I-04A

 Λ

PUMP LOCAL CONTROL PANEL FRONT DOOR LAYOUT

		LO	CAL CONTROL PA	ANEL BILL OF MATERIALS
ITEM NO		MFR	MODEL	DESCRIPTION
1	1	HOFFMAN	CSD363016SS (A)	36"x30"x16" NEMA 4X 316L SS PANEL (A)
2	1	HOFFMAN	CP3630	FULL BACK PANEL FOR ITEM 1
3	AR	ALLEN-BRADLEY	1492-H SERIES	FUSED TERMINAL BLOCKS, END ANCHORS, END BARRIER,
4	AR	ALLEN-BRADLEY	1492-J SERIES	TERMINAL BLOCKS, END ANCHORS, END BARRIER, AND MA
5	AR	ALLEN-BRADLEY	1492-DR4	DIN RAIL MOUNTING CHANNEL
6	AR	ALLEN-BRADLEY	1492-SPM	MINIATURE CIRCUIT BREAKER - 1-POLE
7	AR	ALLEN-BRADLEY	700-HA SERIES	3-POLE, 120VAC RELAY WITH SOCKET
8	AR	ALLEN-BRADLEY	700-FE SERIES	120VAC GENERAL PURPOSE TIMING RELAY
9	AR	PANDUIT	PANELMAX DRD SERIES	WIREWAY AND COVER, SIZE TO ACCOMMODATE GROWTH
10	1	ALLEN-BRADLEY	800T SERIES	45mm EMERGENCY STOP PUSHBUTTON, 1 NO, 1 NC CONTA
11	1	ALLEN-BRADLEY	800T SERIES	30.5mm 3-POSITION SELECTOR SWITCH
12	1	ALLEN-BRADLEY	800T SERIES	30.5mm MOMENTARY CONTACT PUSHBUTTON, RED
13	1	ALLEN-BRADLEY	800T SERIES	30.5mm MOMENTARY CONTACT PUSHBUTTON, GREEN
14	1	ALLEN-BRADLEY	800T SERIES	30.5mm MOMENTARY CONTACT PUSHBUTTON, BLACK
15	1	ALLEN-BRADLEY	800T SERIES	30.5mm PUSH-TO-TEST, FULL VOLTAGE LED PILOT LIGHT, V
16		ALLEN-BRADLEY	800T SERIES	30.5mm PUSH-TO-TEST, FULL VOLTAGE LED PILOT LIGHT, A
17	2	ALLEN-BRADLEY	800T SERIES	30.5mm PUSH-TO-TEST, FULL VOLTAGE LED PILOT LIGHT, 0
18	1	PHOENIX CONTACT	EO-AB SERIES	DIN RAIL-MOUNTED DUPLEX RECEPTACLE
19	1	ALLEN-BRADLEY	1756-A7	7-SLOT PLC CHASSIS
20	1	ALLEN-BRADLEY	1756-PA72	PLC POWER SUPPLY
21	1	ALLEN-BRADLEY	1756-EN2TR	ETHERNET COMMUNICATIONS MODULE
22	2	ALLEN-BRADLEY	1756-IA16I	16-POINT DIGITAL INPUT MODULE
23	1	ALLEN-BRADLEY	1756-OA16I	16-POINT DIGITAL OUTPUT MODULE
24	3	ALLEN-BRADLEY	1756-N2	SLOT FILLER
25	AR	ALLEN-BRADLEY	700-HL	INTERPOSING RELAY
26	1	EDCO	SLAC-12036	120VAC SURGE SUPPRESSOR
27	1	ALLEN-BRADLEY	800T SERIES	30.5mm PUSH-TO-TEST, FULL VOLTAGE LED PILOT LIGHT, F

PUMP LOCAL CONTROL PANEL BACK PANEL LAYOUT

LCP	LCP NAMEPLATE LEGEND				
NAMEPLATE	NAMEPLATE TEXT				
1	PUMP NO. 1 LOCAL CONTROL PANEL (SEE NOTE 1)				
2	CONTROL POWER				
3	RUN TIME				
4	RUNNING				
5	LOW SUCTION PRESSURE				
6	MOTOR OVERLOAD				
7	BEARING OVER TEMP				
8	HIGH DISCHARGE PRESSURE				
9	LOCAL/OFF/REMOTE				
10	START				
11	STOP				
12	RESET				
13	E-STOP				
14	DISCHARGE CONTROL VALVE				
15	OPENED				
16	CLOSED				
17	TRAVELING				

UNDERGROUND UTILITIES 2 WORKING DAYS BEFORE YOU DIG CALL TOLL FREE 800-362-2764 OHIO UTILITIES PROTECTION SERVICE NON-MEMBERS MUST BE CALLED DIRECT UNDERGROUND UTILITIES 2 WORKING DAYS BEFORE YOU DIG CALL TOLL FREE 800-925-0988 OL & GAS PRODUCERS UNDERGROUND PROTECTION SERVICE (OGPUPS) ADDENDUM NO. 5 - FILE NO. 55-24

Ю

, AND MARKER CARDS ARKER CARDS H PROVISIONS ACTS WHITE AMBER GREEN

RED

	GENERAL SHEET NOTES	
1.	PUMP LOCAL CONTROL PANEL LAYOUT IS TYPICAL FOR FOUR PUMP LOCAL CONTROL PANELS 01-LCP-01, 01-LCP-02, 01-LCP-03, AND 01-LCP-04.	
2.	PROVIDE PANEL OF SUFFICIENT SIZE TO ACCOMMODATE ALL REQUIRED TERMINAL BLOCKS, CONTROL RELAYS, AND CONTROL WIRING CONDUIT ENTRIES. REFERENCE THE P&IDS FOR FIELD CONNECTIONS TO THE PUMP LOCAL CONTROL PANELS.	FOR
3.	CONTRACTOR SHALL SUPPLY THE TYPE AND QUANTITY OF PLC CHASSIS, PLC MODULES, AND ANCILLARY HARDWARE AS REQUIRED TO ACCOMMODATE ALL I/O, INCLUDING 20% FUTURE CONTROL SYSTEM GROWTH PROVISIONS.	UED
4.	PANEL SHALL BE IN ACCORDANCE WITH NEC ARTICLE 409/UL508A.	SS
5.	THE PLC PANEL LAYOUT DRAWING SHOWS THE GENERAL ARRANGEMENT OF THE HARDWARE. THE CONTRACTOR IS RESPONSIBLE FOR THE DETAILED PANEL DESIGN, INCLUDING PANEL SIZING AND AND THE QUANTITY AND TYPE OF HARDWARE SHOWN IN THE LIST OF PANEL EQUIPMENT.	
6.	FOR ALL PANELS CONTAINING WIRING NOT DE-ENERGIZED BY THE PANEL MAIN DISCONNECTING MEANS OR CIRCUIT BREAKER, PROVIDE A WARNING NAMEPLATE ON THE FRONT OF THE PANEL STATING "WARNING: YELLOW WIRING NOT DE-ENERGIZED BY PANEL DISCONNECTING MEANS". THE NAMEPLATE SHALL BE YELLOW WITH BLACK 1/4" HIGH LETTER ENGRAVINGS AND SHALL BE ATTACHED TO THE PANEL FACE WITH STAINLESS STEEL SCREWS.	
7.	REFERENCE DIVISION 26 AND DIVISION 40 SPECIFICATIONS FOR ADDITIONAL DETAILS AND REQUIREMENTS ON ALL PANEL DEVICES AND HARDWARE.	

L	
S	0
PLC	
JRE	
	5
	S
_	

R	EVISIO	DNS		CITY OF CLEVELAN	Π
NO	DATE	BY	1		
			-	CLEVELAND DIVISION OF WA DEPARTMENT OF PUBLIC UTILITI CLEVELAND, OHIO	ATER es
			SUBJECT	CYCLE H - GREEN PUMP STAT	TION
			PUMF	P LOCAL CONTROL PANEL DETAI	LS 1 OF 2
			1		
DRAWN	NBY:	SJT	SCALE	CWD NO:	SHEET NO:
DESIGN	NED BY:	SJT	NTS	4	1-09
CHECK	ED BY:	VM	DATE: 12/2021		

PUMP NO. 1 CONTROL SCHEMATIC

Ċ	SENERAL SHEET NOTES
1.	PUMP LOCAL CONTROL PANEL WIRING DIAGRAM IS TYPICAL FOR FOUR PUMP LOCAL CONTROL PANELS 01-LCP-01, 01-LCP-02, 01-LCP-03, AND 01-LCP-04.
2.	PANEL SHALL BE IN ACCORDANCE WITH NEC ARTICLE 409/UL508A.
3.	REFERENCE DIVISION 26 AND DIVISION 40 SPECIFICATIONS FOR ADDITIONAL DETAILS AND REQUIREMENTS ON ALL PANEL DEVICES AND HARDWARE.
	1. 2. 3.

LOCATION LEGEND

LOCAL CONTROL PANEL

FIELD

MCC

RTU PANEL

1	
2	
3	
4	

F	REVISIO	DNS		CITY OF CLEVELAN	D
NO	DATE	BY			
			-	CLEVELAND DIVISION OF WA DEPARTMENT OF PUBLIC UTILITI CLEVELAND, OHIO	ATER ES
			SUBJECT	CYCLE H - GREEN PUMP STAT	ION
			PUMP	LOCAL CONTROL PANEL DETAI	LS 2 OF 2
			-		
DRAW	N BY:	SJT	SCALE	CWD NO:	SHEET NO:
DESIG	NED BY:	SJT	NTS	-	I-10
CHEC	KED BY:	VM	DATE: 12/2021		

										٦	$\left\{ \right\}$			
ollogix . Input IA16I Slot 02	-2	-4	-6	-8	 -12	 (16)	 -20	-22	-24	-26	-28	30	32	~ ~
												•	,	

PUMP NO. 1 LOCAL STATUS YID-11001
PUMP NO. 1 REMOTE STATUS YIB-1101
PUMP NO. 1 ESTOP ACTIVE YAG-1101
PUMP NO. 1 RUN STATUS YIR-1101
PUMP NO. 1 OVERLOAD ALARM YAF-1101B
PUMP NO. 1 SUCTION VALVE OPENED ZIO-1103
PUMP NO. 1 SUCTION VALVE CLOSED ZIC-1103
PUMP NO. 1 DISCHARGE VALVE OPENED ZIO-1104
PUMP NO. 1 DISCHARGE VALVE CLOSED ZIC-1104
PUMP NO. 1 BEARING OVER TEMP TAH-1101
PUMP NO. 1 LOW SUCTION PRESS PAL-1101
PUMP NO. 1 HIGH DISCHARGE PRESS PAH-1101
CONTROL POWER JI-1101
PUMP NO. 1 DISCHARGE CONTROL VALVE OPENED ZIO-1102
PUMP NO. 1 DISCHARGE CONTROL VALVE CLOSED ZIC-1102
PUMP NO. 1 DISCHARGE CONTROL VALVE TRAVELING ZIM-1102

ADDENDUM NO. 5 - FILE NO. 55-24 ADDENDUM NO. 3 - FILE NO. 55-24

LEGEND

 RIO WIRING
 FIELD WIRING
FIELD DEVICE TERMINAL

O LOCAL CONTROL PANEL TERMINAL

GENERAL SHEET NOTES

1. VERIFY FIELD CONTACTS ARE DRY CONTACTS NECTING MAIN CONTROL PANEL GITAL INPUTS.

S FOR 01-LCP-01 ARE TYPICAL 01-LCP-03, AND 01-LCP-04. E P&IDS FOR LOOP AND FIELD

\mathbf{m}

r		
CONTROLLOGIX DIGITAL INPUT 1756-IA16I RACK 1 SLOT 03		1. VERIFY FIELD CO PRIOR TO CONNE 120VAC FOR DIGI
(1) IN 0 (2)	SPARE	2. LOOP DIAGRAMS FOR 01-LCP-02, 0 REFERENCE THE
3 IN 1 4	SPARE	DEVICE NUMBER
(5) IN 2	SPARE	
(7) IN 3	SPARE	
(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)(3)<	SPARE	
11) IN 5	SPARE	
(12) (13) IN 6	SPARE	
(14) (15) IN 7	SPARE	
(16) (17) IN 8	SPARE	
18 19 IN 9	SPARE	
20 21 IN10	SPARE	
22 23 IN11	SPARE	
24 25 IN12	SPARE	
26 27 IN13	SPARE	
28 29 IN14	SPARE	
30 30	SPARE	
32		
	J	

	R	REVISIO	NS		CITY OF CLEVELAN	D		
	NO	DATE	BY					
4	А	12/2020	Sigma			ATED		
4	В	5/2021	Sigma		DEPARTMENT OF PUBLIC UTILITI	A I ER ES		
	С	11/2021	Sigma		CLEVELAND, OHIO			
				SUBJECT	SUBJECT CYCLE H - GREEN PUMP STATION LOCAL CONTROL PANEL LOOP DIAGRAM 2			
				LOC				
	DRAW	N BY:	SJT	SCALE	CWD NO:	SHEET NO:		
	DESIG	NED BY:	SJT	NTS	4	I-20		
	CHEC	KED BY:	VM	DATE: 12/2021		. 20		

CODED NOTES		\Lambda ADDENDU	M NO. 3 - FILE NO. 55-2
	UNDERGROUND UTILITIES		(
	2 WORKING DAYS BEFORE YOU DIG CALL TOLL FREE 800-362-2764 OHIO UTILITIES PROTECTION SERVICE NON-MEMBERS MUST BE CALLED DIRECT UNDERGROUND UTILITIES 2 WORKING DAYS BEFORE YOU DIG CALL TOLL FREE 800-925-0988 MILE SASS PRODUCES UNDERGROUND PROTECTION SERVICE (OFFURS)	FJR ARCADIS	UDATEL PA LOUR SERVICE

JUNCTION BOX TO THE EXISTING.

				WIRING BLOCK DIAGRAM		
	DRAWN BY:		E. KLINE	SCALE AS NOTED	CWD NO:	SHEET NO:
	DESIGNED BY:		E. KLINE			E-12
	CHECKED I	BY:	J. SIDOTI	DATE: 12/2021		